

DEC 16 1996

COMMISSION

JUDITH D. ROEHM 07/11/96
Ontonagon County 08:52
LC 4/105 JEM Feet 9.00
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 43W.	J-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1/4 Corner 2 & 11; T.48 N., R.43 W.

I, Richard L. Drahn in a field survey on June 4, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3										●			
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on August 17, 1848. Original B.T.S --- Sugar 8" S.57 W. 26 links (17.16') --- Sugar 14" N.55 E. 18 links (11.88') --- Corner re-established by Richard L. Drahn, RLS 21564 on 7/23/91 by single proportionate methods. He set a 2 1/2" dia. aluminum pipe with a 3 1/4" stamped aluminum cap and the following new bearing objects: --- 11" (11") Sugar Maple N.74 W. (N.76 W.) 10.53' (10.51') --- 8" (9") Black Ash N.50 E. (N.47 E.) 19.44' (19.42') --- 9" (9") Sugar Maple S.27 W. (S. 29 W.) 22.29' (22.29') --- 6' Metal sign rail S.89 W. (S.87 W.) 1.69' (1.7') --- Corner recorded in Ontonagon County in Liber 3, Page 175 on 4/22/93. Act 74 research form on file with Ontonagon County records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing objects as noted in parentheses above. No evidence found of the original bearing trees.

PEER GROUP APPROVED

Earl W. Applikans
COUNTY REPRESENTATIVE

07-08-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

13" Sugar Maple S.28 E. 20.15'



Signed by *Richard L. Drahn*

Date June 4, 1996

Surveyor's Michigan License No. 21564