

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM
Ontonagon County
LC 3/364 MEL Feet 9.00
10/26/95
14:06
Page 1 of 1

For corners in ONTONAGON Located In: _____ Corner Code # _____
(County)

- | | | | | | | |
|--------------------------------------|---|-----------|---|-----------|------------|-------|
| 1. Public Land Survey | T | <u>48</u> | R | <u>43</u> | <u>J-5</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner common to Section 11 & 14, T48N R43W.

I, Earl W. Applekamp, in a field survey on August 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, August 1848. Set Sugar Post.

ORIGINAL BEARING TREES:

Hemlock 14" S21°W 9 links (5.94 feet)
Yellow Birch 38" N67°E 31 links (20.46 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At the corner position I found a monument marking the position. This monument was set by Edward Kazianka and recorded August 9, 1976 in Liber 1, L.C., page 48. The monument I found was the same as described in the Act 74 form. The location was in agreement to the distance called for in the original notes to the Section Corner East and West, which are also recorded. I accepted the monument as marking the corner position and updated the bearing trees and accessories as described in "C" below. Research on file with County Remonumentation Program Representative.

PEER GROUP APPROVED

Earl W. Applekamp 10-18-95
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position stands a 1" diameter x 36" long iron pipe with a four inch aluminum cap stamped as follows: Kimberly Clark Corp., T48N R43W, $\frac{1}{4}$, S.11, S.14, RLS 14765, 7-28-76. I established the following new bearing trees and reference objects:

7" Maple S40°E 32.00 feet - 12" Maple N85°W 21.65 feet
10" Maple N24°E 26.00 feet - Steel Sign Post, South 1.22 feet



Signed by Earl W. Applekamp

Date October 04, 1995

Surveyor's Michigan License No. 17610