

DEC 16 1996

COMMISSION

JUDITH D. ROEHM
Ontonagon County
LC 4/107 JEM Fee: 9.00
07/11/96 08:52
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>48N</u> R <u>43W</u> .	<u>K-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 Corner 1 & 2; T.48 N., R.43 W.

Richard L. Drahn in a field survey on June 4, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt on August 17, 1848. Original B.T.s--- B. Ash 8" S.71 W. 30 links (19.80') --- B. Ash 8" N.62 1/2 E. 22 links (14.52')

Corner re-established by Richard L. Drahn RLS 21564 on 7/16/91 by single proportionate methods. He set a 3/4" solid aluminum rod with a 3 1/4" stamped aluminum cap and the following new bearing objects: --- 3" (3") Black Ash N.25 E. (N.24E.) 3.63' (3.63') --- 4" (4") Black Ash S.59 E. (S.57 E.) 11.21' (11.21') --- 3" Black Ash (3") S.78 W. 9.71' (9.71') --- 6' Metal sign rail S.54 W. (S.54 E. (S.53 E. 2.62' (2.6') --- Corner recorded in Ontonagon County in Liber 3, Page 177 on 4/22/93.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing objects as noted in parentheses above.

No evidence remains of the original bearing trees.

PEER GROUP APPROVED
Paul W. Applekamp
COUNTY REPRESENTATIVE
07-08-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

3" Black Ash S.15 W. 10.57'



Signed by Richard L. Drahn Date June 4, 1996
Surveyor's Michigan License No. 21564