

SURVEY & REMONUMENTATION

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SE
RE
RE

For corner in **COMMISSION**
ONTONAGON
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>48</u> R <u>43</u> | <u>K-4</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Recorded October 19 1994
at 2:13 o'clock P. M. in
Liber 3 page 215
Judith M. Van Der Pijp
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
1/4 Corner Section 11 & 12, T48N R43W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Earl W. Applekamp, in a field survey on October 01, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Wood Post
- Hemlock 18" S31°W 39 Links (25.74')
- Sugar Maple 7" N41°E 35 Links (23.10')

ONTONAGON COUNTY

PEER APPROVED

Earl W. Applekamp
Ontonagon Co Rep.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence found. Found 1 1/2" axle shaft placed at corner location. This point is identified and used in a recorded plat of the Village of Merriweather dated February 29, 1924. It is also used in several surveys in the area. Based on this evidence I set a permanent monument at the axel shaft position. This monument is described below.

Research on file with County Remonumentation Representative



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2"x30" long split aluminum pipe with a 3 1/4" cap stamped to read: County Remonumentation, 1/4 S-11, 12, T48N R43W, 1994, P.S. 17610. I established the following ties to trees and objects.

- 7" Hemlock S57°W 23.32' 9" Maple S72°E 22.25'
- 7" Maple S41°E 30.79' Steel Sign Post North 1.09'

Signed by Earl W. Applekamp Date October 07, 1994
Surveyor's Michigan License No. 17610