

APR 29 1995

COMMISSION

JUDITH D. ROEHM  
Ontonagon County  
LC 3/407 JEM Feet 9.00  
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ontonagon Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- 1. Public Land Survey T 48N R 42W A-9  
T 48N R 43W M-9  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John R. Garske, in a field survey on November 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original survey by John and William Burt, Deputy Surveyors, in August 1847. Set a sugar post from which:  
8" hemlock - S60°E, 28 links  
8" maple - N25°W, 6 links
- M.D.O.T. Highway Plans show corner at 0.9' east of highway centerline (iron rod)
- 1952 Plat of "Finn & Feathers" shows corner 1.2' east of centerline.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 3/4" diameter iron rod in a monument box, 0.9' east of the centerline of Highway M-64 as shown on the highway plans. I also found a 6" diameter concrete monument due east 78.30 feet. This corner position is commonly used and accepted and I am accepting it as marking the true corner position.

(Record research on file)


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3" diameter brass cap on the iron rod found and stamped it to identify the corner from which I established:

- Reference monument - Set a 3" diameter aluminum cap on the found concrete monument stamped due west - 78.30 feet to corner.
- 20" S. maple - N48°E - 54.48 feet.
- Twin 5" S. maple - S51°E - 80.60 feet
- Steel sign rail - Due East - 49.08 feet

PEER GROUP APPROVED

Carl Spollich  
COUNTY REPRESENTATIVE  
11-06-95



Signed by John R. Garske Date 11-6-95  
Surveyor's Michigan License No. 28410