

**SURVEY &
REMONUMENTATION**

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM
Ontonagon County
LC 4/ 11 JEM Fee: 9.00
Page 1 of 1

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>48NR 43W</u>	<u>K-3</u>
	T <u> R</u>	<u> </u>
	T <u> R</u>	<u> </u>
	T <u> R</u>	<u> </u>
2. Property Controlling in Section	S <u> T</u> R <u> </u>	<u> </u>
	S <u> T</u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> T</u> R <u> </u>	<u> </u>
	S <u> T</u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner common to Sections 1, 2, 11, & 12, T48N R43W.

I, Earl W. Applekamp, in a field survey on July 28, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3											●		
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor on August 15, 1848. Set Sugar Post.

ORIGINAL BEARING TREES:

Lynn 14" S50°W 38 links (25.08 feet) - Hemlock 14" N65°E 3 links (1.98

Corner position monumented by RLS 21583 with a 1 1/4" diameter iron pin, August 1981. Recorded in Liber 2, page 8. Corner was remonumented by RLS 21564 in July 1991, with a 2 1/2"x30" aluminum pipe with a 3/4" cap. Recorded in Liber 3 page 176, April 22, 1993.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On July 28, 1995 I needed this corner for a survey in the area. The monument had been broken off at the ground level. I re-established the corner, using the ties shown on the corner certificate and set a monument as shown in "C" below.

Research on file.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2"x30" long aluminum pipe with a 3/4" cap stamped to read: COUNTY REMONUMENTATION, S1, S11, S12, T48N R43W, 1995, P.S. 17610. I re-painted bearing trees shown on 1993 corner certificate, established an additional bearing tree and set a new sign post.

8" Red Maple N08°E 23.37 feet - 4" Maple N47°W 57.54 feet (new)
7" Red Maple N49°E 30.24 feet - Steel Sign Post, East 2.94 feet (new)
8" Sugar Maple N72°E 23.24 feet

BEER GROUP APPROVED

Earl W. Applekamp 12-14-95
COUNTY REPRESENTATIVE

Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date December 06, 1995

