

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

WILLIAM D. ROEHM
Ontonagon County
LC 3/ 263 JEM

05/03/95
13:49

Fee: .00
Page 1 of 1

For corners in
Ontonagon
(County)

Located In: _____ Corner Code # _____

- 1. Public Land Survey T 49N R 38W J-1
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____
 1/4 Corner Sections 2 & 35; T.49-50N., R.38W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Richard L. Drahn, in a field survey on May 18, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Austin Burt, U.S. Deputy Surveyor, on June 24, 1847. Original bearing trees:

Cedar	12"	N.36E.	50 links	(33.00 feet)
Y. Birch	10"	N.08W.	12 links	(7.92 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence remains, corner established on line between and equal distance from the NE & NW section corners of Section 2; T.49N., R.38W.

**ONTONAGON COUNTY
PEER APPROVED**

*Earl W Applekamp
Ontonagon Co Rep
Mar 01, 1995*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position and 6" below the surface of an E-W road I set a 2" x 12" concrete filled galvanized iron pipe with a 3" brass cap, stamped to read: T.49-50N., R.38W.; 1/4; S-2, S-35; 1994; R.L.S. 21564; from which I established the following: A 2 1/2" x 30" aluminum pipe with a 3 1/4" aluminum cap stamped to indicate the corners location bears; North, 30.54 feet.

6"	Red Pine	N.34W.	42.85 feet
10"	Power Pole	N.58E.	48.35 feet
10"	Power Pole	S.51E.	49.50 feet
6'	Steel Rail	North	30.54 feet

Signed by Richard L. Drahn

Date February 8, 1995

Surveyor's Michigan License No. 21564