

APR 29 1995

COMMISSION

JUDITH D. ROEHM
Ontonagon County

05/09/95
13:52

LC 3/265 JEM

Fee: .00
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon
(County)

Located In:

Corner Code #

1. Public Land Survey	T 49N R 38W	K-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Quarter corner, Sections 1 and 2, T49N-R38W.

I, Richard L. Drahn, in a field survey on May 15, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Artimus Curtis, U.S. Deputy Surveyor, on June 23, 1851. Original bearing trees:

Cedar	12"	N.64°W.	24 links	(15.84 feet)
Sugar	16"	S.74°E.	22 links	(15.18 feet)

This certificate replaces the certificate recorded in Liber 2, Page 394 on April 10, 1986. An error in computations resulted in my monumenting the corner incorrectly on October 8, 1985.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

All original evidence destroyed by road construction. Corner established by single proportionate measurement on line between the northeast and southeast section corners of Section 2. From proportioned point distance checks to natural feature call north "Stream 5 links course NW". 1933 records indicate corner is in middle of north and south road, the proportioned point falls in middle of north and south abandoned road.

ONTONAGON COUNTY
PEER APPROVED

Earl W Applekamp
Ont Co Rep
March 01, 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a standard 2" I.D. by 30" long split base aluminum monument with a 3 1/4" aluminum cap stamped to read: T.49N., R.38W.; 1/4; S.1, S.2; 1985; R.L.S. 21564: from which I established the following new blazed and scribed bearing trees:

6"	Sugar Maple	N.38°W.	10.47 feet
6"	Sugar Maple	S.68°E.	23.10 feet
6"	Sugar Maple	S.82°W.	6.21 feet

a 6' steel sign post bears; S.73°W. 0.30 feet



Signed by Richard L. Drahn

Date February 6, 1995

Surveyor's Michigan License No. 21564