	SURVEY &	
1	REMONUMENTATION	

APR 2 9 1996

COMMISSION

JUDITH D. ROEHM Ontonagon County 10/26/95

3/ 394 JEN

08:08

Page 1 of

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

automic none

For	Corners in ONTONAGO!	Located In:	Corner Code #
1.	Public Land Survey	T 49 R 41 T 49 R 42 T R R	A-11) M-11
2.	Property Controlling in Section	S T R S T R	
3.	Miscellaneous Property in Section	S T R S T R	


Register of Deeds Stamp & File Number


. Recorded Plat Lot No.

5. Private Claims

Section Corner common to 25, 30, 31, & 36, T49N R41 & 42W.

LEarl W. Applekamp, in a field survey on July 17. do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United State's Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:





Original corner established by William A.Burt, U.S. Deputy Surveyor, summer 1847. Set Post.

ORIGINAL BEARING TREES:

12" S27°W Lynn 13 links 8.58 feet) Sugar N20°E 40 links (26.40 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner was found. The corner location was re-established using the original survey notes. Calls to top of a hill, the West branch of the Ontonagon River to the North and to the West were used to relocate the corner in its original position. The location of the Corner set is consistent with the original field notes.

Research on this corner filed with the County Remonumentation Representative.

> REPRESENTATIVE COUNTY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

cap stamped to read: COUNTY REMONUMENTATION, S25, S30, S31, S36, T49N R41W, R42W, 1995, P.S. 17610. I established APPLEKAMP . APPLEKAMP .

3" Aspen S77°W 7" Basswood S64°E

18.71 feet 8.43 feet

4" Aspen N62°E Steel Sign Post South 1.25 feet

13.76 feet No. 17610 ST. 1.25 feet No. 17610 ST. 17610 TOFESSIONA

Surveyor's Michigan License No.

pelekany

Date July 29, 1995

REVISED MAY 14, 1975