

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

JUDITH D. ROEHM
Ontonagon County
LC 3/399 JEM Fee: 9.00
10/26/95
08:10
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in	ONTONAGON <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>49</u> R <u>41</u>		<u>A-12</u> ✓
	T <u>49</u> R <u>42</u>		<u>M-12</u>
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

¼ Corner common to Sections 31 & 36, T49N R41 & 42W.

I, Earl W. Applekamp, in a field survey on July 19, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William A. Burt, U.S. Deputy Surveyor, summer 1847. Set Cedar Post.

ORIGINAL BEARING TREES:

Hemlock	18"	N51°E	32 Links	(21.12 feet)
Lynn	8"	S56°W	5 Links	(3.30 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner was found. Corner was re-established by single proportionate measurement between opposite section corners. This corner is one of 29 corners in 6 Sections remonumented under the County Remonumentation Program. Research is on file with the Ontonagon County Remonumentation Representative.

PEER GROUP APPROVED

Earl W. Applekamp
COUNTY REPRESENTATIVE 10-18-95



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2½"x30" aluminum pipe with a ¾" cap stamped to read: COUNTY REMONUMENTATION, ¼, S31, S36, T49N R41W, R42W, 1995, P.S. 17610. I established the following bearing trees and reference objects:

3" Aspen	N03°E	19.73 feet	-	6" Spruce	West	38.03 feet
3" Aspen	N82°E	28.01 feet	-	Steel Sign Post	South	0.93 feet

Signed by Earl W. Applekamp Date July 28, 1995
Surveyor's Michigan License No. 17610