

**SURVEY & REMONUMENTATION**

APR 29 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

JUDITH D. ROEHM 10/26/95  
 Ontonagon County 08:09  
 LC 3/396 JEM Fee: 9.00  
 Page 1 of 1

For corners in ONTONAGON Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey	T <u>49</u> R <u>41</u>	<u>D-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner common to Sections 29 & 32, T49N R41W.

I, Earl W. Applekamp, in a field survey on July 24, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

Original corner established by S.W. Higgins, U.S. Deputy Surveyor, summer 1847. Set Post.

**ORIGINAL BEARING TREES:**

Maple 10" S20°E 25 Links (16.50 feet)  
 Cedar 12" N30°W 35 Links (23.10 feet)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No evidence of original corner was found. Corner was re-established by single proportionate measurement between opposite section corners. This corner is one of 29 corners in 6 Sections remonumented under the County Remonumentation Program. Research is on file with the County Remonumentation Representative.

PEER GROUP APPROVED

Earl W. Applekamp  
 COUNTY REPRESENTATIVE 10-18-95



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

At the corner position I set a 2 $\frac{1}{2}$ "x30" long aluminum pipe with a 3 $\frac{1}{4}$ " cap stamped to read: COUNTY REMONUMENTATION,  $\frac{1}{4}$ , S29, S32, T49N R41W, 1995, P.S. 17610. I established the following bearing trees and reference objects:

6" Aspen N72°W 43.75 feet - 8" Aspen S73°E 13.26 feet  
 6" Aspen N23°E 23.92 feet - Steel Sign Post South 1.51 feet

Signed by Earl W. Applekamp Date July 26, 1995  
 Surveyor's Michigan License No. 17610