

**SURVEY & REMONUMENTATION**

APR 29 1996

JUDITH D. ROEHM  
Ontonagon County  
LC 3/392 JEM Fee: 9.00  
10/26/95 08:07  
Page 1 of 1

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>49</u>	R	<u>41</u>	<u>E-11</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____
3. Miscellaneous Property in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Section Corner common to Sections 28, 29, 32 & 33, T49N R41W.

I, Earl W. Applekamp, in a field survey on June 24, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

Original corner established by S.W. Higgins, U.S. Deputy Surveyor, summer 1847. Set Post.

**BEARING TREES:**

Cedar	12"	N44°E	8 links (5.28 feet)
White Pine	18"	S10°W	10 links (6.60 feet)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No evidence of the original corner was found. There is an old road running N & S through this corner location which has been in existence since the early 1900's. A 40 acre parcel of land was homesteaded 1/2 mile North. a well defined clearing line was found to be 1/2 mile North of the corner location. A blazed and painted line 15 years old runs West from the corner location. I personally remember a 4"x4" yellow tag on a tree a few feet East of the corner location. I traveled this road numerous times during the last 30 plus years and being a surveyor was conscious of the tag. The tag was not found when this corner was set. I accepted the corner position based on the evidence found and set a monument described in "C" below.

Research on file with County Remonumentation Program Representative.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

At the corner position I set a 2 1/2"x30" aluminum pipe with a 3 1/4" cap 3" below top of dirt road. Cap is stamped to read: COUNTY REMONUMENTATION S28, S29, S32, S33, T49N R41W, 1995, P.S. 17610. I established the following trees and reference objects:

5" Aspen	N53°W	36.00 feet	-	3" Spruce	N44°E	21.20 feet
5" Aspen	S34°W	67.70 feet	-	Steel Sign Post	West	15.35 feet

PEER GROUP APPROVED

Earl W. Applekamp 10-18-95  
COUNTY REPRESENTATIVE

Signed by Earl W. Applekamp Date July 22, 1995

Surveyor's Michigan License No. 17610

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983