

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

JUDITH D. RDEHM
 Ontonagon County
 LC 3/304 JEM Fee: 9.00
 08/09/95
 14:29
 Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ONTONAGON
 (County)

Located In:

Corner Code #

1. Public Land Survey	T 49	R 41	E-13
	T 48	R 41	E-1
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Section	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner 32 & 33, T49N 41W,
 Section 4 & 5, T48N R41W

I, Earl W. Applekamp in a field survey on May 24, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by Wills Burt, U.S. Deputy Surveyor, June 1851
 Set Hemlock Post

Original Bearing Trees:

Hemlock 18" N45°E 57 Links (37.62 Feet)
 W. Pine 24" N57°W 14 Links (9.24 Feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner or bearing trees found. Corner position lies at the intersection of roads going 3 ways. Corner position was restored after re-monumenting all corners of 6 Sections in one block. Bearings and distances of all these lines are known. Corner position is in agreement with field notes of the original Government Survey.

Research on file with County Remonumentation Program Representative.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/4"x30" long split base aluminum pipe with a 3/4" cap stamped to read: COUNTY REMONUMENTATION, S4,S5, T48N R41W, S32, S33, T49N R41W, 1995, P.S. 17610. Monument is buried 2" below ground in a dirt roadway. The following trees and objects were used to tie in the corner.

6" Aspen N70°W 60.12 Feet - 5" Aspen 50°E 41.35 Feet
 5" Aspen N06°W 127.54 Feet - Steel Sign Post West 28.10 Feet

BEER GROUP APPROVED

Earl W. Applekamp 8-08-95

COUNTY REPRESENTATIVE

Signed by Earl W. Applekamp

Date June 01, 1995

Surveyor's Michigan License No. 17610