

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code =#
1. Public Land Survey	T <u>49N</u> R <u>42W.</u>	<u>A-5</u> ✓
	T _____ R _____	
	T <u>49N</u> R <u>43W</u>	<u>M-5</u>
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner 7, 18, 12 & 13; T.49 N., R.42-43 W.

I, Richard L. Drahn in a field survey on November 29, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on August 18, 1847. Original B.T.s --- 14" Cedar S.50 E. 25 links (16.50') --- 18" Cedar N.70 W. 13 links (8.58') ---

Corner restored on 9/6/68 by Donald D. Lappala (12585) from the two original B.T.s, the second one still alive and scribed. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following:

- 12" Cedar S.77 E. 46.0'
- 5" Sugar Maple S.08 E. 32.1'
- 8" Yellow Birch S.65 W. 19.5'

Corner recorded in Ontonagon County in USFS Liber, Page J-25 on 4/1/69.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Research form on file with Ontonagon County records.

Recovered the monument as described and the bearing trees as follows:

- 14" Cedar S.72 E. 45.70'
- Sugar Maple dead and down
- 12" Yellow Birch S.70 W. 19.40'

The first original B.T. is now a 20" downed Cedar with GLO blazes. No evidence of the second GLO B.T. remains.

PEER GROUP APPROVED

Carl W. Applekamp
 COUNTY REGISTER
 12-01-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument I referenced the following:

- 6" Steel sign rail East 2.06'
- 8" Basswood S.02 W. 46.95'
- 9" Yellow Birch N.31 E. 24.88'



Signed by Richard L. Drahn Date November 30, 1997

Surveyor's Michigan License No. 21564