

**SURVEY &
REMONUMENTATION**

APR 29 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

JUDITH D. ROEHM 10/26/95
Ontonagon County 14:10
LC 3/374 MEL Fee: 9.00
Page 1 of 1

For corners in ONTONAGON Located In: _____ Corner Code # _____
(County)

1. Public Land Survey	T <u>49</u>	R <u>42</u>	<u>A-12</u>
	T <u>49</u>	R <u>43</u>	<u>M-12</u>
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous	S _____	T _____	R _____
Property in Section	S _____	T _____	R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
 $\frac{1}{4}$ Corner common to Section 31 & 36, T49N R42W & 49N R43W.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Earl W. Applekamp, in a field survey on August 29, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by John Burt, Deputy Surveyor, August 1848. Set Sugar Post.

ORIGINAL BEARING TREES:

Sugar 12" S48°E 19 links (12.54 feet)
Sugar 6" N56°W 42 links (27.72 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of original corner was found. Near the corner position I found a yellow tag on tree marked E $\frac{1}{4}$ Cor Sec 36, signed by Milo Stephen a former Bergland Ranger. I set the corner on a straight line between the Section Corner North and South of this $\frac{1}{4}$ corner and a latitude equal to the yellow tag. The corner location is consistent with the distance given on the original field notes. I established a monument described in "C" below. Research on file with County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp 10-18-95
COUNTY REPRESENTATIVE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 $\frac{1}{2}$ "x30" aluminum pipe with a 3 $\frac{1}{4}$ " cap stamped to read as follows: T49N R42W R43W, $\frac{1}{4}$, S.31, S.36, 1995, P.S. 17610. I established the following bearing trees and reference objects:

8" Maple S49°W 36.40 feet - 11" Maple N30°E 36.84 feet
16" Maple S13°E 19.65 feet - Steel Sign Post North 1.26 feet

Signed by Earl W. Applekamp

Date September 8, 1995

Surveyor's Michigan License No. 17610