

**SURVEY & REMONUMENTATION**

APR 29 1996

COMMISSION

JUDITH D. ROEHN  
 Ontonagon County  
 LC 3/ 322 JEM Feet 9.00  
 09/25/95  
 14:52  
 Page 1 of 1

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Ontonagon  
 (County)

Located In:	Corner Code --#
T <u>49N</u> R <u>42W</u> .	B-3
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

1/4 Corner 6 & 7; T.49 N., R.42 W.

I, Richard L. Drahn in a field survey on August 22, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3	●												
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt on June 27, 1848. Original B.T.s ---Sugar 10" S.75 W. 10 links (6.60') --- Hemlock 18" North 21links (13.86').

Corner restored by Richard L. Drahn R.L.S. 21564 on 6/22/77 from the remains of the two GLO B.T.s and from line tree remains and natural feature ties east and west. He set a 2" by 5' galvanized iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 10" Sugar Maple (now a dead stub) N.01 W, 13.1' --- 10" (12") Cedar S.74 E. (S.72 E.) 32.9' (32.95') --- 12" (14") Cedar S.85 W. (S.88 W.) 34.0' (34.11') --- 7' Metal sign post North 2.4' (2.43')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Ontonagon County; Liber 1, Page 145 on 4/25/79

Recovered monument as described and bearing trees as shown in parentheses above. Only a stump hole and hemlock knots remain of the original B.T.

Act 74 research form of file with Ontonagon County Records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree established:

10" Yellow Birch N.28 W. 12.98'

PEER GROUP APPROVED

*Earl Applekamp 9-20-95*  
 COUNTY REPRESENTATIVE



Signed by Richard L. Drahn

Date September 10, 1995

Surveyor's Michigan License No. 21564