

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon
 (County)

Located in:

Corner Code ##

- 1. Public Land Survey T 49N R 42W
 T _____ R _____
 T _____ R _____
 T 50N R 42W
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

C-1 ✓

 C-13

**SURVEY &
 REMONUMENTATION**

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Section Corner 5, 6, 31 & 32; T.49-50 N., R.42 W.

I, Richard L. Drahn in a field survey on December 3, 19 97
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on 8/18/1847. Original B.T.s --- Hemlock
 18" N.58 E. 34 links (22.44') --- Hemlock 24" N.42 W. 34 links (22.44') ---
 Hemlock 28" S.59 E. 20 links (13.20') --- Hemlock 22" S.56 W. 63 links
 (41.58') ---

Corner restored by Donald D. Lappala (12585) on 5/3/67 from the remains
 of the four original B.T.s and natural features E and S. He set a 2" X 5'
 iron pipe with a 3" stamped brass cap and the following new B.T.s:

- 10" Sugar Maple N.67 W. 16.9'
- 6" Sugar Maple N.53 E. 26.6'
- 10" Sugar Maple S.52 E. 28.9'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Ontonagon County in USFS Liber, Page Z-5 on 6/3/68.

Research form on file with Ontonagon County records.

Recovered the monument as described and the B.T.s as follows:

- 16" Sugar Maple N.67 W. 16.65'
- 6" Sugar Maple N.58 E. 26.71'
- 14" Sugar Maple S.48 E. 28.97'

Stump holes are all that remain from the original B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing object referenced:

- 6' Steel sign rail N.33 W. 3.34'

FEEL GROUP REMOVED
Paul W. Lappala
 12-19-97



Signed by Richard L. Drahn Date December 4, 1997

Surveyor's Michigan License No. 21564