

**SURVEY &
REMONUMENTATION**

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM
Ontonagon County

09/25/95
14:54

3/323 JEM

Fee: 9.00
Page 1 of 1

For corners in

Ontonagon
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 49 N R 42 W. | C-3 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sec. Cor. 5, 6, 7 & 8; T.49 N., R.42 W.

I, Richard L. Drahn in a field survey on August 22, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Sugar 12" N.22 E., 40 links (26.40') --- Sugar 14" S.20 W., 33 links (21.78')

Corner restored by Donald D. Lappala, R.L.S. 12585 on 8/26/65 from the live, still scribed Sugar B.T. at S.20 W. and the stump hole of the B.T. at N.22 E.

Corner recorded in Ontonagon County in USFS Liber, Page E-5 on 3/6/68.

Mr. Lappala set a 2" by 5' galvanized iron pipe with a 3" stamped brass cap

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

and the following new B.T.s: --- 7" (11") Sugar Maple N.44 W (N.40 W.) 15.8' (16.09') --- 4" Sugar Maple (6") S.73 E. (S.70 E) 12.5' (12.59') --- 6" (10") Sugar Maple S.71 W. (S.74 W.) 40.8' (40.49').

Recovered the monument as described and the bearing trees as shown in parentheses above. The GLO B.T. recover by Mr. Lappala is now a 24" live Sugar Maple with GLO blazes; scribing no longer visible.

Act 74 research form on file with Ontonagon County Records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Reference the following bearing objects:

6' Steel sign rail S.37 E. 2.49'

4" X 4" Cedar sign post N.48 W. 3.54'

PEER GROUP APPROVED

Carl Lappala 9-20-95
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn
Surveyor's Michigan License No. 21564

Date September 10, 1995