

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ontonagon Located In: Corner Code ##  
 (County)

1. Public Land Survey T 49N R 42W C-4  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_

2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
 in Section S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
 Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**SURVEY &  
 REMONUMENTATION**

**APR 07 1998**

**SECTION**

**Register of Deeds Stamp & File Number**

$\frac{1}{4}$  Corner 7 & 8; T.49 N., R.42 W.

I, Richard L. Drahn in a field survey on December 3, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt on 6/20/1848. Original B.T.s --- 30" Hemlock S.10 E. 10 links (6.60') --- 10" Y. Birch N05 E. 12 links (7.92') ---

Corner restored by Richard L. Drahn (21564) on 8/26/77 from the remains of the two original B.T.s. He set a 2" X 5' iron pipe monument with a 3" stamped brass cap and the following references:

- 9" Sugar Maple N.44 W. 13.2'
- 6" Sugar Maple N.46 E. 41.4'
- 7" Sugar Maple S.29 E. 55.6'
- 7' Metal sign post East 2.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Ontonagon County in Liber 1, Page 148 on 4/25/79.

Research form on file with Ontonagon County records.

Recovered Mr. Drahn's monument as described and his B.T.s as follows:

- 13" Sugar Maple N.45 W. 13.10'
- 6" Sugar Maple N.46 E. 41.49' (dead stub)
- 8" Sugar Maple S.30 E. 55.69'
- 7' Steel sign rail East 2.71'

Stump holes are all that remain of the original B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing object referenced:

- 13" Sugar Maple N.44 E. 46.77'

PEER GROUP APPROVED  
*Earl W. Appelman*  
 COUNTY REGISTERED SURVEYOR 12-19-97



Signed by Richard L. Drahn Date December 4, 1997

Surveyor's Michigan License No. 21564