

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 42W	C-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**SURVEY &
 REMONUMENTATION**

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner 7, 8, 17 & 18; T.49 N., R.42 W.

Richard L. Drahn, in a field survey on November 29, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt on June 19, 1848. Original B.T.s --- 14" W. Pine N.62 W. 48 links (31.68') --- 16" Y. Birch S.31 E. 38 links (25.08')

Corner restored on 5/4/67 by Donald D. Lappala (12585) from the stump remains of the two original B.T.s and natural feature ties north and south. He set a 2" X 5' iron pipe with a 3" stamped brass cap and the following:

- 4" Yellow Birch N.72 W. 24.3'
- 8" Elm N.30 W. 14.9'
- 8" Black Ash S.24 W. 28.8'

Corner recorded in Ontonagon County in USFS Liber, Page J-5 on 6/3/68.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the corner as described and the bearing trees as follows:

- Yellow Birch (dead and down)
- Elm N.27 W. (broken snag)
- 12" Black Ash S.26 W. 28.68'

No evidence of the GEO B.T.s remain.

Research form on file with Ontonagon County Records.

PEER GROUP APPROVED
Paul W. Applekamp
 COUNTY REPRESENTATIVE 12-01-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument I referenced the following:

- 4" X 4" Cedar sign post S.56 W. 3.14'
- 6' Steel sign rail N.19 E. 2.95'
- 8" Black Ash N.24 W. 12.03'
- 6" Hemlock S.86 W. 23.56'



Signed by Richard L. Drahn Date November 30, 1997

Surveyor's Michigan License No. 21564

USFS J-5