

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>42W</u>	<u>C-8</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

SURVEY &
 REMONUMENTATION

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 19 & 20 T49N R42W.

I, Earl W. Applekamp, in a field survey on Nov. 11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by William Burt, U.S. Deputy Surveyor, June 19, 1848. Set Sugar Post.

ORIGINAL BEARING TREES:

Y. Birch 10" S70°E 22 Links (14.52 Feet)
 Y. Birch 10" N70°W 15 Links (9.90 Feet)

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 11-30-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Within 9 feet of a calculated position I found an old (70 years) fence running East and South. The area West of this fence, owned by the U.S. Forest Service had been logged to the fence. I accepted the fence corner as being the most logical position for the corner and monumented it as shown below.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2" X 30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T49N R42W, S19, S20, 1/4, 1999, P.S. 17610. I established three bearing trees and a reference object.

Nail in 9" Sugar Maple N78°W 37.29' - Nail in 11" Hemlock S19°E 26.32'
 Nail in 9" Y. Birch N01°W 36.89' - 6' Steel Sign Post East 0.50'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date November 20, 1999