and with a second

APR 2 9 1996

COMMISSION

JUDITH D. ROEHM Ontonagon County

3/ 368 MEL

10/26/95

14:08 Fee:

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Page

|    | ONTONAGON (County)   | Located In:             | Corner Code # |                  |
|----|----------------------|-------------------------|---------------|------------------|
| 1. | Public Land Survey   | т <u>49</u> в <u>42</u> | D-11          |                  |
|    |                      | T R                     |               |                  |
|    |                      | T R                     |               |                  |
|    |                      | T R                     |               |                  |
| 2. | Property Controlling | S T R                   |               |                  |
|    | in Section           | S T R                   |               |                  |
| 3. | Miscellaneous        | S T R                   |               |                  |
|    | Property in Section  | S T R                   |               | Register of Deer |

ds Stamp & File Number

| 4. | Lot No, Recorded Plat |        |    |         |    |   |     |      |      |
|----|-----------------------|--------|----|---------|----|---|-----|------|------|
| 5. | i. Private Claims     |        |    |         |    |   |     |      |      |
|    | 1 Corner              | common | to | Section | 29 | & | 32, | T49N | R42W |

Earl W. Applekamp, in a field survey on August 21 . 19 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by William Burt, U.S. Deputy Surveyor on June 14, 1848. Set Ironwood Post.

ORIGINAL BEARING TREES:

Lynn 15" S25°W 18 links (16.50 feet) Sugar 10" N45°E 43 links (28.38 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. A fence line and plantation line runs North from the corner location. The plantation was planted by a former Forester, the late Donald Fisher, about 40 years ago. a gravel road runs East & West from the same location. An original call to the center of a 2 acre pond East was in agreement. A 6" Maple, 24 feet South of the corner location had an old blaze facing the corner location. I re-established the corner at the centerline of the East-West Road and opposite the lence line running North. This location was in agreement with the called distance to the Section Corners, East and West. I set a monument described in "C" below. Research on file with County

Remonumentation Program

Representative.

sup

Representative.

County Representative

Count Description of monument for corner and access.

At the corner location I set a 3/4"x15" long aluminum rod with a 3½" cap atamped to read: T49N R42W, ¼, S.29, S.32, 1885, P.S. 17610. Monument is NO.

17610

17610

OFESSIONALIMITATION

5" Maple 47.25 feet Reference Monument, South 21.80 feet 4" Maple S24°E 37.32 feet Steel Sign Post 1.35 feet South of Pole N42°W 47.02 feet Reference Monument

Signed by 17610 Surveyor's Michigan License No.

September 8, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975

REVISED JAN., 1983

Date