

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON
(County)

Located In:

Corner Code #

1. Public Land Survey

T49N R42W

E-7

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

SURVEY &
REMONUMENTATION

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Section Corner common to Section 16, 17, 20 & 21, T49N R42W.

I, Earl W. Applekamp, in a field survey on April 4, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by William Burt, U.S. Deputy Surveyor, June 13, 1848. Original bearing trees: 12" Hemlock N76°E, 27 links (17.82 feet). 20" Sugar, S26°W, 26 links (17.16 feet). On Dec. 21, 1978, Richard L. Drahn, RLS, monumented the corner from remains of the two original bearing trees, the remains of an original Hemlock line tree East and a distance checks North and East to 1/4 Corners which were in accordance with G.L.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At the corner position I found a 2" I.D. Concrete filled galvanized iron pipe capped with a 3" brass tablet, stamped to read: T49N R42W, S16, S17, S20, S21, 1978, RLS 21564. This is the same monument set by Richard L. Drahn described above. He established 3 bearing trees, 5" Yellow Birch, N47°W, 15.4 feet (now a 7" Y. Birch), 15" Sugar Maple, S87°E, 33.5 feet (cut down by loggers), 9" Sugar Maple, S40°W, 12.2 feet, a 7 foot Steel Sign Post bears S04°E, 2.6 feet.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

The monument is described in B. I established two additional bearing trees: Nail in 8" Sugar Maple, N39°E, 22.00 feet, Nail in 11" Sugar Maple, S02°E, 32.10 feet.

FREE GROUP APPROVED

Earl W. Applekamp 6-9-99
COUNTY REPRESENTATIVE



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date May 25, 1999