

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>42W</u>	<u>E-8</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**SURVEY &
REMONUMENTATION**

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 20 & 21, T49N R42W.

I, Earl W. Applekamp, in a field survey on Nov. 01, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by William Burt, U.S. Deputy Surveyor, June 13, 1848. Set Cedar Post.

ORIGINAL BEARING TREES:

Cedar 20" S04°W 11 Links (7.26 Feet)
 Cedar 16" S25°E 17 Links (11.22 Feet)

PEER GROUP APPROVED
Earl W. Applekamp 11-09-99
 COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. In 1912 a R.O.W. for a road was cleared from Bergland to the Cascade Creek. The road was never built in this area of the corner, but apparently the bearing trees were destroyed when the R.O.W. was cut. I re-established the corner by single proportionate measure between corners North and South and in the Center-line of the cleared R.O.W.

Research on file with the Ontonagon County Remonumentation Program Representative

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the Corner position I set a 7/8"X5 1/2 foot aluminum rod with a 3" cap stamped to read: County Remonumentation, T49N R42W, S20, S21, $\frac{1}{4}$, 1999, P.S. 17610. I established three bearing trees and a reference object.

Nail in 6" Cedar S35°W 31.70' - Nail in 11" H. Maple S53°E 49.54'
 Nail in 4" Cedar N24°W 35.48' - 6' Steel Sign Post North 0.82'



Signed by *Earl W. Applekamp*
 Surveyor's Michigan License No. 17610

Date November 8, 1999