

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

JUDITH D. ROEHM
 Ontonagon County
 LC 3/391 MEL Fee: 9.00
 10/26/95
 14:19
 Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in	Located In:	Corner Code #
<u>ONTONAGON</u> (County)		
1. Public Land Survey	T <u>49</u> R <u>42</u>	<u>E-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Section 32 & 33, T49N R42W

I, Earl W. Applekamp, in a field survey on August 04, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	15	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner, set by William Burt, U.S. Deputy Surveyor, June, 1848. Set Cedar Post.

ORIGINAL BEARING TREES:

Hemlock 20" South 20 links (13.20 feet)
 Hemlock 18" N55°W 27 links (17.82 feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence was found. Corner was re-established by single proportionate measurement between opposite section corners North and South.

I set a monument described in "C" below.

Research on file with County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp 10-18-95
 COUNTY REPRESENTATIVE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 $\frac{1}{2}$ "x30" aluminum pipe with a 3 $\frac{1}{4}$ " cap stamped to read as follows: T49N R42W, $\frac{1}{4}$, S.32, S.33, 1995, P.S. 17610. I established the following bearing trees and reference objects:

3" Aspen N15°E 39.68 feet - 10" Aspen S08°E 77.69 feet
 6" Aspen N61°E 23.24 feet - Steel Sign Post West 1.17 feet

Signed by *Earl W. Applekamp*
 Surveyor's Michigan License No. 17610

Date September 8, 1995