

**SURVEY & REMONUMENTATION**

APR 29 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM  
Ontonagon County  
LC 3/365 MEL Fee: 9.00  
10/26/95 14:06  
Page 1 of 1

For corners in ONTONAGON Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

- |                                      |   |           |   |           |             |       |
|--------------------------------------|---|-----------|---|-----------|-------------|-------|
| 1. Public Land Survey                | T | <u>48</u> | R | <u>42</u> | <u>E-1</u>  |       |
|                                      | T | <u>49</u> | R | <u>42</u> | <u>E-13</u> |       |
|                                      | T | _____     | R | _____     | _____       |       |
|                                      | T | _____     | R | _____     | _____       |       |
| 2. Property Controlling in Section   | S | _____     | T | _____     | R           | _____ |
|                                      | S | _____     | T | _____     | R           | _____ |
| 3. Miscellaneous Property in Section | S | _____     | T | _____     | R           | _____ |
|                                      | S | _____     | T | _____     | R           | _____ |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

**Register of Deeds Stamp & File Number**

Section Corner common to Sections 4 & 5, T48N R42W and Sections 32 and 33, T49N R42W.

I, Earl W. Applekamp, in a field survey on October 10, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by William A. Burt, U.S. Deputy Surveyor, August 1848. Set Cedar Post.

**ORIGINAL BEARING TREES:**

Maple 10" N21°E 48 links (31.68 feet)  
Sugar 10" N12°W 41 links (27.06 feet)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No original evidence was found. At the corner position I found a 1/2" I.P., 2" below the blacktop at the intersection of Michigan Highway M-64 and M-28. I personally know of this corner being at this position for 30 or more years. This corner position has been used for numerous surveys in the area and is identified in the MDOT Highway drawings. I accepted the corner position and set reference monuments as shown in "C" below. Research on file with the County Remonumentation Representative.

**PEER GROUP APPROVED**

Earl W. Applekamp 10-18-95  
COUNTY REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

At the corner position I left the 1/2" Iron Pin in place and set two 2 1/2"x30" aluminum pipe reference monuments with a 3 1/4" cap stamped to read: T48-49N, R42W, S.4, S.5, S.32, S.33, R.M., 1995, P.S. 17610. Cap has the bearing and distance from the corner stamped on it. Reference monuments are set 1/2" below the ground surface.

Ref. Mon. S50°W 49.37 feet - Power Pole N20°W 82.17 feet  
Ref. Mon. N50°E 50.64 feet - Power Pole S40°W 44.76 feet  
Reference Monuments and 1/2" Iron Pipe on line



Signed by Earl W. Applekamp  
Surveyor's Michigan License No. 17610

Date October 11, 1995