

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON (County)	Located In:	Corner Code #
1. Public Land Survey	T 49NR42W	F-7
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

**SURVEY &
 REMONUMENTATION**
MAR 23 2000
SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 16 & 21, T49N R42W.

I, Earl W. Applekamp, in a field survey on April 24 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7						●							
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by William Burt, U.S. Deputy Surveyor, June 14, 1848. Set Sugar Post. ORIGINAL BEARING TREES: 8" Spruce N60°W, 35 Links. 8" W. Pine, S10°E, 22 Links. Corner was remonumented by Richard L. Drahn on September 21, 1978, from the remains of the two original bearing trees. He monumented it with a 2" I.D.X5' long concrete filled galvanized pipe capped with a 3" circular brass tablet stamped to read: T49N R42W, $\frac{1}{4}$, S16, S21, 1978, RLS 21564. The corner was recorded with the Ontonagon Co. Register of Deeds in Liber 1, Page 158, April 25, 1979.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the monument set as described above. Mr. Drahn had witnessed the monument with three bearing trees, namely an 8" (14") White Pine, S64°E, 19.4 feet, 7" (11") White Pine, S24°W, 32.8 feet, 5" (7") Red Maple, N45°W, 19.4 feet. He set a 7' Sign Post S14°W, 1.8 feet. The bearing trees were in excellent condition.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I accepted the corner re-established by Richard Drahn and established one new bearing tree. A nail in an 8" Hemlock S73°W 28.22 Feet.

BEAR GROUP APPROVED
Earl W. Applekamp
 COUNTY SUPERVISOR
 11-30-99



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date November 19, 1999