

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>T49NR 42W</u>	<u>F-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling In Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**SURVEY &  
 REMONUMENTATION**

**MAR 23 2000**

**SECTION**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

1/4 Corner common to Sections 21 & 28, T49N R42W.

I, Earl W. Applekamp, in a field survey on April 13 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Burt, U.S. Deputy Surveyor, June 13, 1848. Set Sugar Post.

ORIGINAL BEARING TREES:

10" Hemlock	N06°	19.80 feet
15" Sugar Maple	S45°E	6.60 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner position falls in Old Highway M-64. No other evidence was found. Corner was re-established by single proportionate measure between opposite section corners, East and West.

Research on file with the Ontonagon County Remonumentation Program Representative.

DEED GROUP APPROVED  
*Earl W. Applekamp*  
 COUNTY SURVEYOR  
 5-11-99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"x12" rebar with a stamped cap in the center-line of Old Highway M-64 and 6" below top of gravel. I established a reference monument, a 2 1/2"x30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T49N R42W, S21, S28, 1/4, R.M., 1999, P.S. 17610. I also established three other objects.

Nail in Twin 8" H. Maple	N40°W	46.82'	- REF.MON.	S08°W	28.28'
Nail in 5" H. Maple	N65°E	71.71'			
Nail in 6" H. Maple	S33°E	41.84'			



Signed by Earl W. Applekamp  
 Surveyor's Michigan License No. 17610

Date May 3, 1999