

**SURVEY &
REMONUMENTATION**

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM
Ontonagon County
LC 3/325 JEM Fee: 9.00
09/25/95
14:59
Page 1 of 1

For corners in

<u>Ontonagon</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>42</u> W.	<u>G-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Sec. Cor. 3,4,9 &10; T. 49N., R.42W.

I, Richard L. Drahn in a field survey on August 22, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3							●						
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt on June 10, 1848. Original B.T.s Sugar 10" S.30 E. 25 links (16.5') --- Sugar 14" N.30 W. 29 links (19.14').

Corner restored by Richard L. Drahn, R.L.S. 21564 on 8/24/77 from the stump holes of the original B.T.s and from line trees, natural feature ties and distances to recovered corners north, south, east and west. He set s 2" by 5' galvanized iron pipe with a 3" stamped brass cap and the following new B.T.s: 8" (10") Sugar Maple N.01 E. (N.04 E. 35.4' (35.46') --- 6" (7") Sugar Maple S.64 E. (S.63 E.) 20.2' (20.29') --- 5" (6") Sugar Maple S.70 W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(S.69 W. 22.0' (21.99') --- 7' Metal sign post N.11 E. (N.14E.) 2.1' (2.03').

Corner recorded in Ontonagon County in Liber 1, Page 161 on 4/25/79.

Recovered the monument as described and the bearing trees as shown in parentheses above.

Act 74 research form on file with Ontonagon County Records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Referenced the following new bearing tree:

7" Sugar Maple N.49 W. 32.49'

PEER GROUP APPROVED

Paul [Signature] 9-20-95
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn
Surveyor's Michigan License No. 21564

Date September 10, 1995