

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>T49N</u> R <u>R42W</u>	<u>G-8</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling In Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

**SURVEY &
 REMONUMENTATION**

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner common to Sections 21 & 22, T49N R42W.

I, Earl W. Applekamp, in a field survey on May 25, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21	●	22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William A. Burt, U.S. Deputy Surveyor, June 9, 1848. Set Sugar Post.

ORIGINAL BEARING TREES:

18" Sugar	N23°E	35 Links (23.10 feet)
18" Sugar	S18°W	27 Links (17.82 feet)

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REGISTERED 6-9-99

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Old Michigan Highway M-64 runs North and South along the Section line. Corner was re-established by single proportionate measure and on line between opposite Section corners North & South. Corner falls in the centerline of Old Highway m-64.

Research on file with the Ontonagon County Remonumentation Program Representative.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 5/8"X12" rebar with a 3" aluminum cap 6" below top of gravel, stamped to read: County Remonumentation, T49N R42W, S21 S22, 1/4, 1999, P.S. 17610. I established a reference monument,, a 2 1/2"X30" split base aluminum pipe with a 3" cap stamped the same as above. A 6' steel sign post bears West 0.8 feet from the reference monument. I also established three bearing trees.

REF. MON.	N86°-45'-19"E	36.27 feet	- Nail in 6 1/2" Maple	S36°W	59.55 feet
	N68°W	53.77 feet	- Nail in 7" Maple	S36°E	52.94 feet

Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date June 8, 1999