

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T49N R 42W	G-9
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

**SURVEY &
 REMONUMENTATION**

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 21, 22, 27 & 28, T49N R42W.

I, Earl W. Applekamp, in a field survey on April 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William Burt, U.S. Deputy Surveyor, June 8, 1848. Set Y. Birch Post.

ORIGINAL BEARING TREES:

18" Cedar N60°E 19.14 feet
 12" Y. Birch S31°W 21.12 feet

PEER GROUP MEMBER
Earl W. Applekamp
 COUNTY SURVEYOR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. At the apparent corner position there is a 90° bend in Old Michigan Highway M-64. At the intersection I found a 7/8" diameter iron pin. This pin had been used for several surveys in the area. I accepted the iron pin as the only logical position for the corner.

5-11-99

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2" X 30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T49N R42W, S21, S22, S27, S28, 1999, P.S. 17610. I established 3 bearing trees and set an iron post with sign.

Nail in 4" Black Ash S26°W 50.10' - Nail in 12" Aspen N40°E 45.61'
 Nail in 11" Aspen S70°W 57.60' - 6' Steel Sign Post East 0.61'



Signed by *Earl W. Applekamp*
 Surveyor's Michigan License No. 17610

Date April 20, 1999