

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49NR42W</u>	<u>G-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**SURVEY &
 REMONUMENTATION**

MAR 28 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 27, 28, 33 & 34, T49N R42W.

I, Earl W. Applekamp, in a field survey on Nov. 02, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	19		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by William Burt, U.S. Deputy Surveyor, June 08, 1848. Set Sugar Post.

ORIGINAL BEARING TREES:

Hemlock 30" S55°W 24 Links (15.84 Feet)
 Black Ash 16" S60°E 22 Links (14.52 Feet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. At the corner position there was the remains of an old fence running South and West. This fence outlined an 80 Acre farm which was worked beginning in the 1930'S. There being no dispute of this location I accepted the position of the fence corner as best representing the original Corner location.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp 11-09-99
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the Corner position I set a 2½"X30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T49N R42W, S27, S28, S33, S34, 1999, P.S. 17610. I established three bearing trees and a reference object.

Nail in 10" Maple N37°W 37.66' - Nail in 7" Maple S17°W 23.40'
 Nail in 9" Maple S69°E 38.14' - 6' Steel Sign Post West 0.60'



Signed by *Earl W. Applekamp*
 Surveyor's Michigan License No. 17610

Date November 8, 1999