

**SURVEY & REMONUMENTATION**

APR 26 1996

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**  
For corners in  
ONTONAGON  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T 48 R 42 T 49N R 42W T _____ R _____ T _____ R _____	G-1 G-13 ✓
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	

Recorded December 19 1994  
at 2:30 o'clock P. M. 11  
Liber Survey 3 page 247  
*Earl W. Applekamp*  
Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Section Corner 3, 4, 33 & 34, T48, 49N R42W

I, Earl W. Applekamp, in a field survey on December 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by John Burt, U.S. Deputy Surveyor, August 1848. Set Elm Post.

Original Bearing Trees:

Black Ash	12"	N41°E	38 Links	(25.08 feet)
Black Ash	12"	N56°W	24 Links	(15.84 feet)

**ONTONAGON COUNTY**  
**PEER APPROVED**  
*Earl W. Applekamp*  
*Ont Co Rep*  
*12-15-94*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At the corner location is a  $\frac{1}{2}$ " iron pin in a box on the centerline of Highway M-28. This monument has been at this location for 30 plus years. It is shown on the highway drawings. I accepted the monument at being the true location of the corner.

Research on file with the County Remonumentation Program Representative



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I used the existing  $\frac{1}{2}$ " iron pin to mark the location of the corner. I set two reference monuments, one North and one South, which are  $2\frac{1}{4}$ "x30" aluminum pipes with a  $3\frac{1}{4}$ " cap stamped to read: County Remonumentation, R.M. S.3, S.4, S.33, S.34, T48N, T49N, R42W. 1994, P.S. 17610. These two monuments and the Section Corner are on line. The following reference monuments and objects were used to tie in the corner.

Reference Monument	North 42.64 feet	-	Steel Sign Post North	44.25 feet
Reference Monument	South 45.03 feet	-	Steel Sign Post South	46.54 feet

Signed by Earl W. Applekamp  
Surveyor's Michigan License No. 17610

Date December 12, 1994

247