

**SURVEY &
REMONUMENTATION**

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. RDEHM
Ontonagon County
LC 3/ 321 JEM Fee: 9.00
Page 1 of 1

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>42W.</u>	<u>I-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 Corner 2 & 3; T.49 N., R.42 W.

I, Richard L. Drahn in a field survey on August 21, 19 95
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
Corner established by William Burt on June 7, 1848. Original B.T.s
--- Lynn 14" S.61 W., 24 links (15.84') --- Hemlock 20" N.80½ E., 8 links (5.28').

Corner restored by Richard L. Drahn, R.L.S. 21564 on 8/29/77 from the remains of the original Hemlock B.T. and from natural feature ties and distances to recovered corners north and south. He set a 2" by 5' galvanized iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 5" (6") Sugar Maple N.18 E. (N.20 E.) 48.1' (48.11') --- 8" Sugar Maple (9") S.78E. (S.76 E) 27.4' (27.43') --- 5" (6") Sugar Maple S.81 W. (S.82 W.) 50.6' (50.77')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
7' Metal sign post S.07 W. (S.12 W.) 1.8' (1.94'). Corner recorded in Ontonagon County; Liber 1, Page 167 on 4/25/79.

Recovered monument as described and bearing trees as shown in parentheses above. No hemlock wood or bark remains in the stump hole of the GLO B.T.

Ace 74 research form on file with Ontonagon County Records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
New bearing tree established:

6" Basswood S.16 E. 3.12'

PEER GROUP APPROVED

Paul Applekamp 9-20-95
COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date September 10, 1995
Surveyor's Michigan License No. 21564