

**SURVEY & REMONUMENTATION**

APR 29 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHN  
 Ontonagon County  
 LC 3/326 JEM Fee: 9.00  
 09/25/95 15:01  
 Page 1 of 1

For corners in

<u>Ontonagon</u> <small>(County)</small>	Located In:	Corner Code #:
1. Public Land Survey	T <u>49N</u> R <u>42 W.</u>	<u>I-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

Sec. Cor. 2, 3, 10 & 11; T.49 N., R.42 W.

I, Richard L. Drahn, in a field survey on August 21, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3									●				
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 Corner established by William Burt in 1848. Original B.T.s --- Sugar Maple 12" S.71 W. 27 links (17.82) --- Sugar Maple 12" N.46 E. 30 links (19.80')

Donald D. Lappala restored this corner on 15/10/69 from the stump remains of the NE B.T. and natural feature ties and a line tree east and south. He set a 2½" by 5' galvanized iron pipe with a 3" stamped brass cap and the following new bearing trees: --- 8" (13") Sugar Maple N.41 W. (N.40 W.) 45.7' (45.54') --- 10" (15") Sugar Maple S.89 E. (S.89 E) 49.3' (49.30') --- 9" (14") Sugar Maple S.13 E. (S.10 E) 48.0' (38.15').

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Act 74 research form on file with Ontonagon County Records.

Recovered the monument as described and the bearing trees as shown above in parentheses. Fragments of Sugar Maple wood still found in root holes of the original NE B.T.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Referenced the following new bearing object:

6' Steel Rail S.47 W. 1.70'

**PEER GROUP APPROVED**  
*Earl Applekamp*  
 COUNTY REPRESENTATIVE



Signed by Richard L. Drahn Date September 10, 1995  
 Surveyor's Michigan License No. 21564