

DEC 16 1996

COMMISSION

JUDITH D. ROEHM

Ontonagon County

LC 4/121 JEM

07/11/96

09:07

Fee: 9.00

Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 43W.	D-1
	T ___ R ___	_____
	T ___ R ___	_____
	T 49N R 43W	D-13 ✓
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1/4 Corner 5 & 32; T.48-49 N., R.43 W.

Richard L. Drahn, in a field survey on June 12, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		6		5		4		3		2		1
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on Aug. 16, 1847. Original B.T.s --- Sugar 14" N.28 E. 13 links (8.58') --- Sugar 12" N.30 W. 46 links (30.36'). Corner re-established by Richard L. Drahn, RLS 21564 on 6/22/88 by single proportionate methods. He set a 2 1/4" dia. aluminum pipe with a 3 1/4" stamped aluminum cap and the following new bearing objects: --- 8" (9") Sugar Maple N.46 W. (N.44 W.) 19.99' (17.96') --- 11" (12") Sugar Maple N.24 E. (N.26 E.) 5.79' (5.76') --- 7" (8") Sugar Maple S.25 E. (S.26 E.) 45.12' (45.10') --- 6' Steel rail S.06 E. (S.05 E.) 2.2' (2.15').---

Corner recorded in Ontonagon County in Liber 3, Page 90 on 5/8/89.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Act 74 research form on file with Ontonagon County records.

Recovered the monument as described and the bearing trees as noted in parentheses above. No GLO evidence remains.

PEER GROUP APPROVED

Paul W. Applekamp
COUNTY REPRESENTATIVE

07-08-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

13" Sugar Maple S.79 E. 7.74'



Signed by Richard L. Drahn

Date June 13, 1996

Surveyor's Michigan License No. 21564