

**SURVEY &
REMONUMENTATION**

DEC 16 1996

JUDITH D. ROEHM
Ontonagon County
LC 4/115 JEM Fee: 9.00
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

<u>Ontonagon</u> <small>(County)</small>	Located In:	Corner Code --#
1. Public Land Survey	T <u>49N</u> R <u>43W</u>	<u>F-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

$\frac{1}{4}$ Corner 21 & 28; T.49 N., R.43 W.

I, Richard L. Drahn in a field survey on June 18, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt on July 3, 1848. Original B.T.s --- Y. Birch 24" N.60 E. 15 links (9.90') --- Sugar 12" S.67 W. 38 links (25.08') --- Corner restored by Richard L. Drahn RLS 21564 on 10/22/81 from the remains of the two original B.T.s. He set a 2" dia. aluminum pipe with a 3 1/4" stamped aluminum cap and the following new bearing objects: --- 6" (8") Sugar Maple N.79 W. (N.80 W.) 33.85' (33.73') --- 6" (7") Sugar Maple N.29 E. (N.27 E.) 26.97' (26.95') --- 7" (12") Sugar Maple S.10 E. (S.11 E.) 38.30' (38.38') --- 6' Metal sign post S.83 E. 2.0' (2.1') --- Corner recorded in Ontonagon County in Liber 2, Page 69 6/15/82.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Act 74 research form on file with Ontonagon County records.

Recovered the monument as described and the bearing trees as noted in parentheses above.

Portions of a Yellow Birch windfall remain from the Y. Birch B.T. and a deep stump hole still remains from the original Sugar B.T.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing tree referenced:

14" Sugar Maple S.88 E. 28.99'

PEER GROUP APPROVED

Earl W. Applekamp
COUNTY REPRESENTATIVE

07-08-96



Signed by Richard L. Drahn

Date June 20, 1996

Surveyor's Michigan License No. 21564