O REMONGRAEMY TON

DEC 1 6 1995

For corners in

4. Lot No.

COMMISSION

JUDITH D. ROEHM Ontonason County 07/11/96 69:08

LC 4/ 123 JEM Feet

9.00

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Page 1 of 1

	Ontonagon (County)	Located In:	Corner Code ##
1.	Public Land Survey	т <u>49N</u> R <u>43</u> W Т В	G-12
	•	T R	
		T R	
2.	Property Controlling	S T R	
	in Section	S R	
3.	Miscellaneous	S T R	
	Property in Sec.	S T R	:

Corner 33 & 34; T.49 N., R.43 W.

Register of Deeds Stamp & File Number

5. Private Claims ______

_ , Recorded Plat

Richard L. Drahn, in a field survey on June 17, 19 96 of hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt on June 30, 1848. Original B.T.s --B. Ash 10" S.35 E. 11 links (7.26') --- B. Ash 10" N.30 W. 12 links (7.92')
--- Corner restored by Richard L. Drahn, RLS 21564 on 10/22/81 from the
remains of the two original B.T.s (the first a 21" live Black Ash with
GLO blazes). He set a 2" dia. iron pipe monument with a 3" stamped brass
cap and the following new B.T.s:--- 13" (16") Cedar N.30 W. (N.31 W.) 36.97'
(36.96') --- 7" (9") Black Ash N.65 E. (N.62 E.) 20.96' (20.92') --- 7" (10")
Black Ash S.04 W. (S.03 W.) 49.96' (49.92') --- 6' Metal sign post S.04 W.
(S.03 W.) 1.8' (1.75') ---

B. Corner recorded in Ontonagon (County) The Interior of the sound and of method applied in restoring or reestablishing corner 6/15/70.

Bearing objects referenced:

4" Red Maple S.55 E. 6.41'

Act 74 research form on file with Ontonagon County records.

Recovered the monument as described and the bearing trees as noted in parentheses above.

The live B.T. recovered in 1981 is now a cut Black Ash with GLO blazes.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

COUNTY REFRESENTATIVE 07-08-96



Signed by Richard L. Drahm

Date June 17, 1996

Surveyor's Michigan License No. 21564