

SURVEY & REMONUMENTATION

DEC 18 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM 07/11/96
 Ontonagon County 09:09
 LC 4/125 JEM Fee: 9.00
 Page 1 of 1

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code-#
1. Public Land Survey	T <u>49N</u> R <u>43W</u>	<u>H-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1/4 Corner 27 & 34; T. 49 N., R.43 W.

I, Richard L. Drahn in a field survey on June 18, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		22
7													
8	19		20		21		22		23		24		
9													
10	30		31		32		33		34		35		36
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt on June 30, 1848. Original B.T.s --- Cedar 14" N.50 W. 27 links (17.82') --- Cedar 12" S.20 E. 12 links (7.92') Corner restored by Donald D. Lappala, RLS 12585 on 11/1/68 from the remains of the two original B.T.s, (one still scribed). He set a 2" dia. iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 12" (16") Cedar N.54 W. (N.56 W.) 22.6' (22.45') --- 12" Hemlock (now dead and down) N.85 E. (N.87 E.) 16.8' --- 7" Cedar (now a dead stub) S.20 W. (S.20 W.) 36.3' --- Corner recorded in Ontonagon County in USFS Liber, Page V-15 on 4/1/69. Act 74 research form on file with Ontonagon County records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as noted in parentheses above.

The original B.T. at S.20 E. is now a decayed Cedar windfall with portions of the GLO blaze still visible. No evidence remains of the B.T. at N.50W.

PEER GROUP APPROVED

Earl W. Applekamp
 COUNTY REPRESENTATIVE

07-08-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing objects referenced:

- 4" X 4" Cedar sign post S.27 E 1.0'
- 6' Steel sign rail N.83 W. 4.55'
- 18" Hemlock N.79 E. 33.96'
- 16" Yellow Birch S.13 W. 18.82'



Signed by Richard L. Drahn

Date June 20, 1996

Surveyor's Michigan License No. 21564

USFS V-15