

DEC 16 1996

COMMISSION

JUDITH D. ROEHM
Ontonagon County
LC 4/126 JEM

07/11/96
09:09
Fee: 9.00
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon (County)	Located In:	Corner Code --#
1. Public Land Survey	T <u>48N</u> R <u>43W</u>	<u>J-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T <u>49N</u> R <u>43W</u>	<u>J-13</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

1/4 Corner 2 & 35; T.48-49 N., R.43 W.

I, Richard L. Drahn in a field survey on June 5, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on Aug. 16, 1847. Original B.T.s --- Hemlock 24" N.35 E. 4 links (2.64') --- Y. Birch 20" N.05 W. 21 links (13.86') --- Corner restored by Richard L. Drahn RLS 21564 on 6/12/80 from the remains of the two original b.T.s. and a single proportionate analysis of 1 1/2 miles of township lines. He set a 2" dia iron pipe with a 3" stamped brass cap and the following new bearing objects. --- 6' (9") Sugar Maple N.40 E. (N.40 E.) 22.10' (22.08') --- 4" (5") Sugar Maple S.35 E. (S.37 E.) 9.15' (9.15') --- 12" (17") Yellow Birch S.18 W. (S.17 W.) 35.24' (35.23') --- 7' Metal sign post N.45 E. (N.45 E.) 1.5' (1.45') --- Corner recorded in Ontonagon County in Liber 1, Page 240 on 4/15/81.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Act 74 research form on file with Ontonagon County records.

Recovered the monument as described and the bearing objects as noted in parentheses above.

Only stump holes remain from the two original bearing trees.

PEER GROUP APPROVED
Earl W. Applekamp
COUNTY REPRESENTATIVE
07-08-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing object: referenced:
5" Yellow Birch N.41 W. 44.58'



Signed by Richard L. Drahn Date June 8, 1996

Surveyor's Michigan License No. 21564

USFS A-19 (T.48 N.)
Z-19 (T.49 N.)