

**SURVEY &  
REMONUMENTATION**

JUDITH D. ROEHM  
Ontonagon County  
LC 4/108 JEM Fee: 9.00  
07/11/96  
08:53  
Page 1 of 1

DEC 16 1996

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N</u> R <u>43W</u>	<u>K-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner 25 & 26; T.49 N., R.43 W.

I, Richard L. Drahn in a field survey on June 4, \_\_\_\_\_, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt on June 23, 1848. Original B.T.s --- Sugar 16" S.62 E. 35 links (23.10') --- Hemlock 14" N.65 W. 23 links (15.18')  
Corner restored by Donald D. Lappala, RLS 12585 on 10/30/68 from the remains of the two original B.T.s, one still scribed. He set a 2" dia. iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 15" Hemlock (19") S.61 W. (S.62 W.) 31.2' (31.00') --- 5" (8") Sugar Maple N.66 E. (N.65 E.) 15.5' (15.56') --- 7" (9") Yellow Birch S.42 W. (S.40 W.) 26.4' (26.26') --- Corner recorded in Ontonagon County in USFS Liber, Page T-21 on 4/1/69.  
Act 74 research form on file with Ontonagon County records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing trees as noted in parentheses above.

No evidence remains of the original Sugar Maple bearing tree. The Hemlock B.T. is now a 20" Hemlock stump with portions of the GLO B.T. blaze still visible.

PEER GROUP APPROVED  
*Carl W. Applekamp*  
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 07-08-96

Bearing objects referenced:

- 4" X 4" Cedar sign post S.39 W. 2.1'  
6' Steel sign rail N.17 E. 2.6'



Signed by Richard L. Drahn

Date June 8, 1996

Surveyor's Michigan License No. 21564