

**SURVEY &
REMONUMENTATION**

DEC 16 1996

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

JUDITH D. ROEHM 07/11/96
Ontonagon County 08:55
LC 4/113 JEM Fee: 9.00
Page 1 of 1

For corners in **COMMISSION**

| <u>Ontonagon</u> <small>(County)</small> | Located In: | Corner Code # |
|---------------------------------------------|---------------------------|---------------|
| 1. Public Land Survey | T <u>49N</u> R <u>43W</u> | <u>K-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

Sec. Cor. 25, 26, 35 & 36; T.49 N., R.43 W.

I, Richard L. Drahn in a field survey on June 4, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 8 | | 5 | | 4 | | 3 | | 2 | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 6 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt on June 23, 1848. Original B.T.s --- Fir 10" N.35 E. 24 links (15.84') --- Cedar 12" S.10 W. 36 links (23.76')
Corner restored by Donald D. Lappala, RLS 12585 on 8/20/68 from the scribed remains of the Cedar bearing tree. He set a 2" dia. iron pipe with a 3" stamped brass cap and the following new B.T.s: --- 4" (6") Sugar Maple N.04 E. (N.05 E.) 27.6' (27.58') --- 5" (8") Sugar Maple S.68 E. (S.69 E.) 5.9' (5.95') --- 4" (5") Sugar Maple S.04 E. (S.03 E.) 22.2' (22.22') ---
Corner recorded in Ontonagon County in USFS Liber, Page V-21 on 4/1/69.

Act 74 research form on file with Gogebic County records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the monument as described and the bearing objects as noted in parentheses above. No evidence remains of the original bearing trees.

PEER GROUP APPROVAL

Paul W. Lappala
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 07-08-96

Bearing objects referenced:

4" X 4" Cedar sign post S.80 W. 3.95'
6' Steel sign rail S.25 E. 2.2'



Signed by Richard L. Drahn

Date June 8, 1996

Surveyor's Michigan License No. 21564