

DEC 16 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM 07/11/96  
Ontonagon County 08:51  
LC 4/104 JEM Fee: 9.00  
Page 1 of 1

For corners in

Ontonagon (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N, R 43 W.	K-1
	T _____ R _____	_____
	T _____ R _____	_____
	T 49N, R 43W.	K-13
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Sec. Cor 1, 2, 35 & 36; T.48-49 N., R.43 W.

I, Richard L. Drahn, in a field survey on June 4, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 Corner established by John Burt on August 16, 1847. Original B.T.s --- Hemlock 10" N.31 E. 7 links (4.62') --- Sugar 18" N.22 W. 21 links (13.86')  
 Corner re-established by Richard L. Drahn RLS 21564 on 6/12/80 by single proportionate methods between recovered  $\frac{1}{4}$  corners  $\frac{1}{2}$  mile east & west. He set a 2" dia. iron pipe with a 3" stamped brass cap and the following new bearing objects: --- 8" (11") White Ash S.59 E. (S.60 E.) 8.38' (8.36') --- 5" Sugar Maple (now dead and down) S.35 W. (S.37 W.) 47.19' --- 14" (15") White Ash N.53 W. (N.51 W.) 47.17' (47.07') --- 6' Metal sign post S.34 W.(S.35 W.) 1.8' (1.8') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Corner recorded in Ontonagon County in Liber 1, Page 242 on 4/15/81.

Act 74 research form on file with Gogebic County records.

Recovered the monument as described and the bearing objects as noted in parentheses above.

No evidence remains of the original bearing trees.

PEER GROUP APPROVED  
*Earl W. Appleton*  
 COUNTY REPRESENTATIVE

07-08-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

New bearing trees referenced:

6" Sugar Maple S.65 W. 25.78'



Signed by Richard L. Drahn

Date June 4, 1996

Surveyor's Michigan License No. 21564