

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 42W	A-3
	T R	
	T 49N R 43W	M-3 ✓
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**SURVEY &
 REMONUMENTATION**

APR 07 1998

SECTION
 Register of Deeds Stamp & File Number

Section Corner 6, 7, 1 & 12; T.49 N., R.42-43 W.

I, Richard L. Drahn in a field survey on November 29, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by John Burt on August 18, 1847. Original B.T.s --- Hemlock 38" S.24 E. 42 links (27.72') --- Hemlock 7" N.10 W. 33 links (21.78') --- Y. Birch 12" N.45 E. 7 links (4.62') --- Y. Birch 12" S.65 E. 27 links (17.82') ---

Corner restored on 8/12/68 by Donald D. Lappala (12585) from the remains of all four of the original B.T.s; both Y. Birches had GLO blazes and the second Hemlock was still scribed. He set a 2" X 5' iron pipe with a stamped 3" brass cap and the following:

4" Sugar Maple N.70 W. 28.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

9" Hemlock North 40.4'

4" Sugar Maple S.71 E. 14.4'

Corner recorded in Ontonagon County in USFS Liber, Page E-25 on 4/1/69.

I recovered the monument as described and Mr. Lappalas' B.T.s as follows:

7" Sugar Maple N.70 W. 28.16'

12" Hemlock North 40.23'

6" Sugar Maple S.68 E. 14.51'

The remains of the original B.T.s are as follows: stump hole for the first Hemlock; fragments of Hemlock bark and wood for the second; no evidence of the third B.T.; and a 19" near dead Y. Birch with GLO blazes for the fourth original B.T.

Research form on file with Ontonagon County records.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

From the above described monument I established the following references:

4" X 4" Cedar sign post S.49 W. 2.43'

6' Steel sign rail N.29 E. 2.71'

PEER GROUP APPROVED

Earl W. Applekamp
 COUNTY ESTABLISHED 12-01-97



Signed by Richard L. Drahn

Date November 30, 1997

Surveyor's Michigan License No. 21564