

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>49N.</u> R <u>44W.</u>	<u>K-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**SURVEY &  
 REMONUMENTATION**

MAY 22 1997

**COMMISSION**

Register of Deeds Stamp & File Number

Sec. Cor. 25, 26, 35 & 36; T.49 N., R.44 W.

I, Richard L. Drahn in a field survey on September 26, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by William Burt in 1848. Original B.T.s --- Y. Birch 20" S.60 W. 21 links (13.86') --- Y. Birch 12" N.70 E. 43 links (28.38')

Corner restored by Donald D. Lappala, RLS 12585 on 8/8/68 from the remains of the two original B.T.s and a live GLO witness tree. He set a 2" iron pipe monument with a 3" stamped brass cap and the following new bearing trees: --- 7" (9") Sugar Maple N.32 W. (N.32 W.) 11.9' (11.92') --- 8" (12") Sugar Maple N.85 E. (N.87 E.) 17.3' (17.27') --- 12" Yellow Birch (14") S.43 W. (S.45 W.) 41.9' (41.98') ---

Corner recorded in Ontonagon County in USFS Liber, Page V-21 on 4/1/69.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Act 74 research form on file with Ontonagon County records.

Recovered the monument as described and the bearing trees as noted in parentheses above.

The first GLO B.T. is now a stump hole with Y. Birch bark; the second one is now a badly decayed 20-24" Y. Birch stump. The witness tree recovered in 1969 is now a live, 29" Hemlock with GLO blaze and scribing still visible.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Bearing objects referenced:

- 6' Steel rail S.54 E. 3.38'
- 12" Sugar Maple S.38 E. 17.63'

PEER GROUP APPROVED

*Carl W. Applecamp*  
 COUNTY REPRESENTATIVE 10-16-96



Signed by Richard L. Drahn Date September 26, 1996

Surveyor's Michigan License No. 21564