

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 49N R 44W	K-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**SURVEY &
 REMONUMENTATION**

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Cor. 35 & 36; T.49 N., R.44 W.

Richard L. Drahn, in a field survey on October 7, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt in 1848. Original B.T.s --- Hemlock 30" S.75 E. 8 links (5.28') --- Sugar 6" N.85 W. 14 links (9.24') ---

Corner restored by Donald D. Lappala, RLS 12585, on 8/21/68, from the stump of the Hemlock and from the 24" live Sugar with GLO blazes and recovered line tree remains north and south. He set a 2" iron pipe monument with a stamped brass cap and the following new B.T.s: --- 5" (7") Sugar Maple N.09 E. (N.10 E.) 44.3' (44.24') --- 4" (6") Sugar Maple S.71 E. (S.69 E.) 34.7' (34.75') --- 9" (11") Yellow Birch S.03 W. (S.04 W.) 28.8' (28.67') ---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner recorded in Ontonagon County in USFS Liber, Page X-21 on 4/1/69.

Act 74 research form on file with Ontonagon County records.

Recovered the monument as described and the bearing trees as noted in parentheses above. A series of root holes remain from the original Hemlock B.T. and the Sugar is now a live 28" tree with the original chest high blaze.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Bearing objects referenced:

4" X 4" Cedar sign post S.86 E. 2.3'

6" Steel sign rail N.62 W. 1.83'

PEER GROUP APPROVED

Earl W. Applkamp
 COUNTY REPRESENTATIVE 10-16-96



Signed by Richard L. Drahn Date October 9, 1996

Surveyor's Michigan License No. 21564