

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>38W</u>	<u>C-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**SURVEY &  
 REMONUMENTATION**

**OCT 30 1997**

**COMMISSION**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Joseph C. Domitrovich, in a field survey on September 12 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3			●										
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

**(C-3) Corner Common to Sections 5, 6, 7 & 8, T50N, R38W**

A. Description of original monument and accessories and/or subsequent restoration:

1847 - Sylvester W. Higgins set post.  
 10" Sugar S 45° E 15 links  
 12" Hemlock N 58° W 41 links

1954 - Michigan State Highway Department Construction drawings for M-26 show a found 1 1/2" iron pipe. They also show a distance North 4604.89 feet to the Closing corner.

Ties: 4" Maple N 50° E 11.09'  
 3" Maple S 75° E 6.30'  
 5" Maple S 75° W 8.82'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of the original corner or accessories. I found a 1 3/4" O.D. iron pipe 18" above ground. I also recovered 2 M.S.H.D. bearing trees, the 3" Maple (still a 3" tree), and the 4" Maple (now a 5" tree). Distances from these B.T.s to the pipe work well, but the bearing to the 4" Maple was obviously in error. Distance North to the Closing Corner works well with GLO and M.S.H.D. Distance East to the Northeast Corner of Section 8 is 78.6 feet longer than GLO. Distance to the South is 19 feet shorter than GLO, and the bearing is 4° off. The pipe, however, has been the long accepted Section corner, and I believe the discrepancies with GLO are the result of either error or fraudulent work in the original survey. I have accepted the found pipe as the section corner and monumented it as such.

PEER GROUP APPROVED

*Earl W. Applbaum*  
 COUNTY REPRESENTATIVE

9-17-97

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" x 48" aluminum rod driven inside a 1 3/4" O.D. iron pipe with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; S. 5, S. 6, S. 7, S. 8; 1997; T.50N, R.38W; P.S. 37273.

5" Hard Maple N 20° E 11.03' (placed new nail over remains of M.S.H.D. nail)  
 3" Hard Maple S 67° E 6.38' (M.S.H.D. nail and tag)  
 Steel sign post South 1.35' (to face)  
 7" Hard Maple West 23.85'  
 8" Hard Maple N 35° W 11.26'  
 Closing Cor. Sec. 4 & 5 N 00° 49' 36" E 4604.88'  
 SE Cor. Section 5 N 89° 01' 39" E 5358.64'  
 W 1/4 Cor. Section 8 S 04° 09' 31" E 2621.74'

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J. C. Domitrovich

Date 9/16/97

Surveyor's Michigan License No. 37273

