

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ontonagon Located In: Corner Code #  
 (County)

1. Public Land Survey T 50N R 38W G-1  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R

3. Miscellaneous S T R  
 Property in Sec. S T R

**SURVEY & REMONUMENTATION**

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Joseph C. Domitrovich, in a field survey on October 7, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

(G-1) Closing Corner on the 5th Correction Line, Sections 3 & 4, T 50N, R 38W

A. Description of original monument and accessories and/or subsequent restoration:

1847 - Sylvester W. Higgins intersected North Boundary at 13 chains 65 links West of 1/4 post in Section 31, T 51N, R 37W, and set post.  
 12" Balsam S 55° E 29 links  
 8" Hemlock S 46° W 38 links

Undated - Old mining map of Lake and Algoma Mines shows this corner but does not indicate what it is. Distances to corners East and South are noted:  
 S 1/4 Cor. Section 31, T 51N, R 37W N 89° 55' E 900.9'  
 W 1/4 Cor. Section 3 S 00° 40' 30" E 1963.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner and accessories have been destroyed by road construction and logging. An old East-West road bed and an old fence from the South intersect at the corner. I created a corner position at the intersection of the fence to the South and on line between the SW corner and South 1/4 corner of Section 31, T 51N, R 37W. This position works well with GLO and old map distances. It falls 6 feet South of approximate centerline of old East-West road bed. I monumented this position as the closing corner.

PEER GROUP APPROVED

*Paul W. Applekamp*  
 COUNTY REPRESENTATIVE 10-08-97

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 5/8" x 24" iron pin with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; C.C.; S. 4, S. 3; 1997; T.50N, R.38W; P.S. 37273.

3" Elm	N 11° E	26.10'
11" Cedar	S 30° E	23.89'
Steel Sign Post	South	0.92' (to face)
8" Cedar	S 28° W	33.89'
22" White Pine	N 29° W	29.50'
SW Cor. Section 31, T 51N, R 37W	S 89° 58' 59" W	1880.77'
S 1/4 Cor. Section 31, T 51N, R 37W	N 89° 58' 59" E	897.59'
W 1/4 Cor. Section 3	S 00° 41' 17" E	1965.42'



NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J. C. Domitrovich Date 10/8/97

Surveyor's Michigan License No. 37273