

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>38W</u>	<u>G-2</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SURVEY &  
 REMONUMENTATION

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Joseph C. Domitrovich, in a field survey on October 7, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		●	3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

(G-2) 1/4 Corner Common to Sections 3 & 4, T 50N, R 38W

A. Description of original monument and accessories and/or subsequent restoration:

1847 - Sylvester W. Higgins set post  
 10" Hemlock S 65° E 10 links  
 10" Hemlock N 35° W 28 links

Undated - Old Mining map of Algoma and Lake Mines shows this corner but does not indicate what it is. Distances and bearings are shown to Section corners to North and South:  
 NW Cor. Section 3 N 00° 40' 30" W 1963.5'  
 SW Cor. Section 3 S 00° 07' 00" W 2609.1'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner and accessories have been destroyed by logging and farming. I found a 1" x 48" iron pipe at a fallen fence corner. This position works well with bearings and distances shown on old mining map. It has also been used as the corner by Timber Cruisers as the 1/4 corner. It works reasonably well with GLO distance to the North. The distance to the South is not inconsistent with other GLO measured distances in this Township.

I accepted the pipe as the 1/4 corner.

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2" x 30" aluminum pipe with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; 1/4; S. 3, S.4; T.50N, R. 38W; 1997; P.S. 37273.

Witnesses:

8" White Birch	N 28° E	48.00'
8" Soft Maple	S 43° E	14.46'
8" Soft Maple	S 78° W	36.79'
8" Hard Maple	N 50° W	26.75'
Steel Sign Post	North	1.04'
NW Cor. Section 3	N 00° 41' 17" W	1965.42'
SW Cor. Section 3	S 00° 06' 14" W	2608.96'

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J. C. Domitrovich

Date 10/8/97

Surveyor's Michigan License No. 37273

PEER GROUP APPROVED  
*Carl W. Applekamp*  
 COUNTY REPRESENTATIVE  
 10-08-97

