

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50NR 38W</u>	<u>G-3</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

COUNTY
 REMONUMENTATION

OCT 30 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Joseph C. Domitrovich, in a field survey on August 8, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

(G-3) Corner of Sections 3, 4, 9 & 10, T50N, R38W

A. Description of original monument and accessories and/or subsequent restoration:

1847 - Sylvester Higgins, D.S., set post.
 12" Cedar N 53° W 14 links
 12" Y. Birch S 60° E 19 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner and accessories have been destroyed by farming. I found a 2" iron pipe flush with the ground at the intersection of fences to the North, East, and South, and old road bed to West. This pipe falls N 81° E 64.1 feet from theoretical double prorated position. Distance measured to NW corner Section 9 from the pipe is 145 feet longer than GLO notes indicate. This is, however, consistent with distances measured across sections 4, 9, & 16. I believe this is the result of either error or fraudulent work in the original survey. Bearings and distances measured to corners North, East, and South of this pipe work well and has been the long accepted corner. I believe the pipe at the fence intersection best represents the position of the original corner and have accepted it.

Research on file with County Remonumentation Representative.

PEER GROUP APPROVED

Paul W. Applekamp
 COUNTY REPRESENTATIVE 8-13-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a split 2" aluminum pipe driven over the top of a 2" iron pipe, capped with a 3" diameter aluminum cap stamped: COUNTY REMONUMENTATION; S. 4, S. 3, S. 9, S. 10; T.50N, R.38W; 1997; P.S. 37273.

Witnesses:

4" Poplar	N 12° W	37.26'	
4" Soft Maple	N 26° E	39.82'	
3" W. Birch	N 50° E	79.43'	
Base of 1" Rebar	S 03° W	28.61'	(found bent)
Steel Sign Post	West	0.91'	(to face)
W 1/4 Cor. Sec. 10	S 00° 30' 32" W	2643.91'	
N 1/4 Cor. Sec. 10	S 89° 40' 58" E	2617.31'	

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by Joseph C. Domitrovich
 Surveyor's Michigan License No. 37273

Date 8/13/97

